BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/04/2022-23, Date: 07.07.2022

Indet No: BBMP/2022-23/OW/WORK_INDENT52457

SCHEDULE -B

Name of Work: Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	23636.94	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) Data Rate	Cum	212.00	Rupees Two Hundred Twelve Only
2	17634.54	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.In all kinds of soils Depth upto 1.5 m.Item No.1.4.1,	Cum	386.00	Rupees Three Hundred Eighty Six Only
3	162.70	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)	Cum	6719.00	Rupees Six Thousand Seven Hundred Nineteen Only
4	13610.70	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1404.00	Rupees One Thousand Four Hundred Four Only
5	10787.18	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge.	Sqm	234.00	Rupees Two Hundred Thirty Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

6	945.78	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately).Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate.	Sqm	6923.00	Rupees Six Thousand Nine Hundred Twenty Three Only
7	13892.46	Providing B S Slabs of selected quality roughly dressed having a size of 10cms thick and fixed in cement mortar (1:6) including fixing curing etc., complete.as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	Sqm	887.00	Rupees Eight Hundred Eighty Seven Only
8	13892.46	Providing one line dressing to granite stone slab / granite stone masonry as per specifications. as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	Sqm	242.00	Rupees Two Hundred Forty Two Only
9	34731.00	Providing Machine Cutting edges to B S Slabs 2.5cms.wide as per Specifications.(Only Chamfered length Shall be recorded)inclusive of all taxes Complete.,as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	Sqm	414.00	Rupees Four Hundred Fourteen Only
10	2169.36	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	359.00	Rupees Three Hundred Fifty Nine Only
11	379.00	Providing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.20) Approved Data rate	Nos	10492.00	Rupees Ten Thousand Four Hundred Ninety Two Only
12	800.00	Providing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.9 x 0.20) Approved Data rate	Nos	8051.00	Rupees Eight Thousand Fifty One Only
13	36.95	Providing & laying precast drain slab of 230 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.23) Approved Data rate	Sqm	5440.98	Rupees Five Thousand Four Hundred Forty And Paise Ninety Eight Only
14	14696.76	Removing and resetting of kerb stones.	Nos	118.00	Rupees One Hundred Eighteen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

15	19883.64	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165mm respectively,400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork,curing including cost of aterials,labour charges of machinery,loading and unloading,lead and lift,transportation etc., complete as directed by the Engineer in charge of the work (Excluding GST and Area Leading Charges)	Nos	507.00	Rupees Five Hundred Seven Only
16	7093.32	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces.Painting Two Coats on New Concrete Surfaces.	Sqm	102.00	Rupees One Hundred Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner